

**APPENDIX A: BID SCHEDULE**  
**PROJECT CIP# LB-17: FIRST RESPONDERS PARK**

Bidder agrees to perform all work described in the Contract Documents for following unit prices or lump sum prices

LINE	ITEM NO.	DESCRIPTION	ESTIMATED QUANTITIES	MATERIAL	LABOR	TOTAL UNIT PRICE OF MATERIAL AND LABOR	TOTAL IN FIGURES
<b>DEMOLITION</b>							
1	201	Clearing & Grubbing	1 LUMP				\$ -
			TOTAL LUMP SUM PRICE IN WORDS				
2	202	Pipe Removed	82 L.F.				\$ -
			TOTAL LUMP SUM PRICE IN WORDS				
3	202	Pipe Filled in Place	10 L.F.				\$ -
			TOTAL LUMP SUM PRICE IN WORDS				
4	202	Catch Basin or Inlet Removed	2 EA.				\$ -
			TOTAL UNIT PRICE IN WORDS				
5	SPL	Remove Existing Benchmark and Preserve Brass Plug for FCEO Pickup	1 LUMP				\$ -
			TOTAL UNIT PRICE IN WORDS				
<b>EARTHWORK/EROSION CONTROL</b>							
6	203	Excavation	1,800 C.Y.				\$ -
			TOTAL UNIT PRICE IN WORDS				
7	203	Embankment	200 C.Y.				\$ -
			TOTAL UNIT PRICE IN WORDS				
8	204	Subgrade Compaction	3,060 S.Y.				\$ -
			TOTAL UNIT PRICE IN WORDS				
9	204	Proof Rolling	4 HR				\$ -
			TOTAL UNIT PRICE IN WORDS				
10	207	Perimeter Filter Fabric Fence	690 L.F.				\$ -
			TOTAL UNIT PRICE IN WORDS				
11	207	Inlet Protection	20 EA.				\$ -
			TOTAL UNIT PRICE IN WORDS				

**Bidder agrees to perform all work described in the Contract Documents for following unit prices or lump sum prices**

**APPENDIX A: BID SCHEDULE  
PROJECT CIP# LB-17: FIRST RESPONDERS PARK**

LINE	ITEM NO.	DESCRIPTION	ESTIMATED QUANTITIES		MATERIAL	LABOR	TOTAL UNIT PRICE OF MATERIAL AND LABOR	TOTAL IN FIGURES
			600	S.Y.				
12	207	Construction Seeding & Mulching	TOTAL UNIT PRICE IN WORDS				\$	-
13	207	Stabilized Construction Entrance	30	C.Y.			\$	-
14	207	Concrete Washout Area	1	EA.			\$	-
15	SPL	Tree Protection Fencing	70	L.F.			\$	-
<b>SITE IMPROVEMENTS</b>								
16	301	Bituminous Aggregate Base	38	TON			\$	-
17	304	Aggregate Base	195	C.Y.			\$	-
18	402	Asphalt Concrete (Intermediate Course, Per Plan)	74	TON			\$	-
19	404	Asphalt Concrete (Surface Course, Per Plan)	85	TON			\$	-
20	407	Tack Coat, Bituminous	90	GAL.			\$	-
21	608	Curb Ramps	3	EA.			\$	-
22	609	Curb, Straight 18" Concrete	550	L.F.			\$	-
23	630	Traffic Sign, Handicapped Parking Sign, Complete	1	EA.			\$	-

**Bidder agrees to perform all work described in the Contract Documents for following unit prices or lump sum prices**

**APPENDIX A: BID SCHEDULE  
PROJECT CIP# LB-17: FIRST RESPONDERS PARK**

ITEM NO.	DESCRIPTION	ESTIMATED QUANTITIES	MATERIAL	LABOR	TOTAL UNIT PRICE OF MATERIAL AND LABOR	TOTAL IN FIGURES
24	Parking Lot Stall Marking, Complete	280 L.F.				\$ -
		TOTAL UNIT PRICE IN WORDS				
25	Accessible Parking Stall Striping, Complete	1 LUMP				\$ -
		TOTAL LUMP SUM PRICE IN WORDS				
<b>STORM</b>						
26	Manhole, Type "A" (AA-S100)	3 EA.				\$ -
		TOTAL UNIT PRICE IN WORDS				
27	Catch Basin, ODOT 2-3	2 EA.				\$ -
		TOTAL UNIT PRICE IN WORDS				
28	Curb and Gutter Inlet, Per City of Hilliard Cl-1	1 EA.				\$ -
		TOTAL UNIT PRICE IN WORDS				
29	Orifice Plate, Per Plan	1 EA.				\$ -
		TOTAL UNIT PRICE IN WORDS				
30	Manhole Adjusted to Grade	1 EA.				\$ -
		TOTAL UNIT PRICE IN WORDS				
31	4" Pipe Underdrain, Per Plan	815 L.F.				\$ -
		TOTAL UNIT PRICE IN WORDS				
32	4" PVC Pipe, with Type 1 Bedding, with Item 912 Compacted Backfill	346 L.F.				\$ -
		TOTAL UNIT PRICE IN WORDS				
33	6" PVC Pipe, with Type 1 Bedding, with Item 912 Compacted Backfill	48 L.F.				\$ -
		TOTAL UNIT PRICE IN WORDS				
34	8" PVC Pipe, with Type 1 Bedding, with Item 912 Compacted Backfill	190 L.F.				\$ -
		TOTAL UNIT PRICE IN WORDS				

**Bidder agrees to perform all work described in the Contract Documents for following unit prices or lump sum prices**

**APPENDIX A: BID SCHEDULE  
PROJECT CIP# LB-17: FIRST RESPONDERS PARK**

LINE	ITEM NO.	DESCRIPTION	ESTIMATED QUANTITIES		MATERIAL	LABOR	TOTAL UNIT PRICE OF MATERIAL AND LABOR	TOTAL IN FIGURES
35	901	10" HDPE Pipe, with Type 1 Bedding, with Item 912 Compacted Backfill	293	L.F.				\$ -
			TOTAL UNIT PRICE IN WORDS					
36	901	12" HDPE Pipe, with Type 1 Bedding, with Item 912 Compacted Backfill	50	L.F.				\$ -
			TOTAL UNIT PRICE IN WORDS					
37	901	24" HDPE Pipe, with Type 1 Bedding, Backfill Per Plan	12	L.F.				\$ -
			TOTAL UNIT PRICE IN WORDS					
38	901	12" Class IV, with Type 1 Bedding, with Item 912 Compacted Backfill	39	L.F.				\$ -
			TOTAL UNIT PRICE IN WORDS					
39	SPL	Nyloplast Drainage Inlets/Structures - Area Drain with 8" Dome Casting (Light Duty - Black)	3	EA.				\$ -
			TOTAL UNIT PRICE IN WORDS					
40	SPL	Nyloplast Drainage Inlets/Structures - 12"x12" Hinged Pedestrian Grate with Locking Mechanism	11	EA.				\$ -
			TOTAL UNIT PRICE IN WORDS					
41	SPL	Stormtech SC-740 Chambers (Complete with Excavation, Backfill, & Accessories)	47	EA.				\$ -
			TOTAL UNIT PRICE IN WORDS					
<b>UTILITIES</b>								
42	805	3/4" Water Tubing, Per Plan	160	L.F.				\$ -
			TOTAL UNIT PRICE IN WORDS					
43	805	3/4" Water Service Tap, Complete, As Per Plan (see addendum #1)	1	EA.				\$ -
			TOTAL UNIT PRICE IN WORDS					
44	SPL	Hot Box, Model LB1.5 with 500 WPH Heater (King Model U1250), Complete	1	EA.				\$ -
			TOTAL UNIT PRICE IN WORDS					

**APPENDIX A: BID SCHEDULE**  
**PROJECT CIP# LB-17: FIRST RESPONDERS PARK**

Bidder agrees to perform all work described in the Contract Documents for following unit prices or lump sum prices

LINE	ITEM NO.	DESCRIPTION	ESTIMATED QUANTITIES	MATERIAL	LABOR	TOTAL UNIT PRICE OF MATERIAL AND LABOR	TOTAL IN FIGURES
45	SPL	3/4" Backflow Preventer Assy., Valves, and Mounting Assy., Complete	1 EA.				\$ -
TOTAL UNIT PRICE IN WORDS							\$ -
<b>GENERAL</b>							
46	616	Calcium Chloride	0.25 TON				\$ -
TOTAL UNIT PRICE IN WORDS							\$ -
47	618	Water	0.50 MGAL				\$ -
TOTAL UNIT PRICE IN WORDS							\$ -
48	624	Mobilization	1 LUMP				\$ -
TOTAL LUMP SUM PRICE IN WORDS							\$ -
<b>PAVEMENT</b>							
49	608	4" Concrete Sidewalk (Broomed/Tooled), As Per Plan	4,085 S.F.				\$ -
TOTAL UNIT PRICE IN WORDS							\$ -
50	608	Integrally Colored Concrete (Light Sandblast), As Per Plan	2,578 S.F.				\$ -
TOTAL UNIT PRICE IN WORDS							\$ -
51	608	Integrally Colored Concrete Steps (Light Sandblast), As Per Plan	945 S.F.				\$ -
TOTAL UNIT PRICE IN WORDS							\$ -
52	608	Integrally Colored Concrete Header Curb, As Per Plan	87 L.F.				\$ -
TOTAL UNIT PRICE IN WORDS							\$ -
53	608	6" Concrete Service Area Slab (Broomed/Tooled), As Per Plan	17 S.Y.				\$ -
TOTAL UNIT PRICE IN WORDS							\$ -
54	608	Pavers: (4" Conc. Subbase) Pine-Hall English Iron Spot, As Per Plan	1,948 S.F.				\$ -
TOTAL UNIT PRICE IN WORDS							\$ -
55	608	Pavers: (4" Conc. Subbase) Red Range, As Per Plan	1,256 S.F.				\$ -
TOTAL UNIT PRICE IN WORDS							\$ -

**APPENDIX A: BID SCHEDULE**  
**PROJECT CIP# LB-17: FIRST RESPONDERS PARK**

Bidder agrees to perform all work described in the Contract Documents for following unit prices or lump sum prices

LINE	ITEM NO.	DESCRIPTION	ESTIMATED QUANTITIES	MATERIAL	LABOR	TOTAL UNIT PRICE OF MATERIAL AND LABOR	TOTAL IN FIGURES	
56	608	Bluestone (4" Conc. Sub base) Full Range, As Per Plan	1,389 S.F.				\$ -	
			TOTAL UNIT PRICE IN WORDS					\$ -
<b>WALLS</b>								
57	610	18" Seatwall, w/Brick Veneer, Limestone Cap, As Per Plan	202 L.F.				\$ -	
			TOTAL UNIT PRICE IN WORDS					\$ -
58	610	Granite Flag Pole Bases	3 EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS					\$ -
59	610	6'-0" Granite Veneer Memorial Walls, As Per Plan	58 L.F.				\$ -	
			TOTAL UNIT PRICE IN WORDS					\$ -
60	610	Granite Veneer World Trade Center Metal Artifact Pedestal, As Per Plan	1 EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS					\$ -
61	610	Concrete Artifact Platform (Flush with Pavement)	1 EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS					\$ -
62	690	6' Screenwall (Service Area) w/Brick Veneer, Limestone Cap. As Per Plan	42 L.F.				\$ -	
			TOTAL UNIT PRICE IN WORDS					\$ -
63		Service Area Gate, As Per Plan	1 LUMP				\$ -	
			TOTAL LUMP SUM PRICE IN WORDS					\$ -
<b>FOUNTAINS</b>								
64		Granite Water Feature 1 - Reflection Pool (To Include 6'-0" Memorial Walls)	1 LUMP				\$ -	
			TOTAL LUMP SUM PRICE IN WORDS					\$ -
65		Granite Water Feature 2 - Plaza Fountain	1 LUMP				\$ -	
			TOTAL LUMP SUM PRICE IN WORDS					\$ -

**APPENDIX A: BID SCHEDULE**  
**PROJECT CIP# LB-17: FIRST RESPONDERS PARK**

**Bidder agrees to perform all work described in the Contract Documents for following unit prices or lump sum prices**

LINE	ITEM NO.	DESCRIPTION	ESTIMATED QUANTITIES	MATERIAL	LABOR	TOTAL UNIT PRICE OF MATERIAL AND LABOR	TOTAL IN FIGURES	
<b>LANDSCAPE</b>								
66	653	Com-Til (Planting Soil)	202 C.Y.				\$ -	
			TOTAL UNIT PRICE IN WORDS					
67	659	Soil Amendment/Seed Mix (Fertilizer/Conditioners), As Per Plan	1,656 S.F.				\$ -	
			TOTAL UNIT PRICE IN WORDS					
68	661	Mulch	35 C.Y.				\$ -	
			TOTAL UNIT PRICE IN WORDS					
69		Seeded Turf	184 S.Y.				\$ -	
			TOTAL UNIT PRICE IN WORDS					
70	690	Aeration Tube w/Cap and Screened Gate	13 EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS					
71	661	Deciduous Shade Tree, 3" Caliper Single Cane, Amelanchier x Grandiflora 'Autumn Brilliance'	6 EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS					
72	661	Deciduous Shade Tree, 3" Caliper, Syringa Reticulata 'Ivory Silk'	7 EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS					
73	661	Deciduous Shrub, 24" height, 3 Gal., Euonymus Alata 'Rudy Haag'	61 EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS					
74	661	Deciduous Shrub, 48" height, B+B, Thuja Occidentalis 'Nigra'	39 EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS					
75	661	Perennial, 8" height, 1 Gal., Liriope Muscari 'Big Blue'	200 EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS					
76	661	Perennial, 36" height, 2 Gal., Panicum Virgatum 'Heavy Metal'	72 EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS					

**Bidder agrees to perform all work described in the Contract Documents for following unit prices or lump sum prices**

**APPENDIX A: BID SCHEDULE  
PROJECT CIP# LB-17: FIRST RESPONDERS PARK**

LINE	ITEM NO.	DESCRIPTION	ESTIMATED QUANTITIES		MATERIAL	LABOR	TOTAL UNIT PRICE OF MATERIAL AND LABOR	TOTAL IN FIGURES	
77	661	Perennial, 12" height, 1 Gal., Pennisetum Alopecuroides 'Hamelin'	32	EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS						
78	661	Perennial, 6" height, 1 Gal., Pennisetum Alopecuroides 'Little Bunny'	100	EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS						
79	661	Perennial, 6" height, 2-1/4" P.P., Euonymus Fortunei 'Colorata'	355	EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS						
80	661	Perennial, 6" height, 2-1/4" P.P., Vinca Minor	64	EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS						
81	661	Deciduous Vince, 24" height, 1 Gal., Wisteria Macrostachys 'Blue Moon'	4	EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS						
<b>SITE FURNISHINGS/MISCELLANEOUS</b>									
82	690	Limestone Bench	13	EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS						
83	680	Café Tables	4	EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS						
84	680	Trash Recepticles	2	EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS						
85	690	Bike Rack	7	EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS						
86		Intentionally Left Blank							
			TOTAL UNIT PRICE IN WORDS						
87	690	Fiberglass Flagpoles, As Per Plan	5	EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS						

**Bidder agrees to perform all work described in the Contract Documents for following unit prices or lump sum prices**

**APPENDIX A: BID SCHEDULE  
PROJECT CIP# LB-17: FIRST RESPONDERS PARK**

LINE	ITEM NO.	DESCRIPTION	ESTIMATED QUANTITIES	MATERIAL	LABOR	TOTAL UNIT PRICE OF MATERIAL AND LABOR	TOTAL IN FIGURES
88	690	Flag	5 EA. TOTAL UNIT PRICE IN WORDS				\$ -
89	690	Railings/Guardrails	19 L.F. TOTAL UNIT PRICE IN WORDS				\$ -
90	893	Trelliss Structure, As Per Plan	1 LUMP TOTAL LUMP SUM PRICE IN WORDS				\$ -
91		World Trade Center Metal Artiface Placement (2 Pieces)	1 LUMP TOTAL LUMP SUM PRICE IN WORDS				\$ -
<b>ELECTRICAL</b>							
92	625	Luminaire, Decorative Post Top, 150 Watt HPS Type III, 240V, As Per Plan	10 EA. TOTAL UNIT PRICE IN WORDS				\$ -
93	SPL	Luminaire, Type "GWA", Wall Upright, 240Volts, As Per Plan	16 EA. TOTAL UNIT PRICE IN WORDS				\$ -
94	SPL	Luminaire, Type "GWS", Wall Upright, 240Volts, As Per Plan	17 EA. TOTAL UNIT PRICE IN WORDS				\$ -
95	SPL	Luminaire, Type "FP", In Ground Upright, 240Volts (Flag Pole Lighting)	9 EA. TOTAL UNIT PRICE IN WORDS				\$ -
96	SPL	Luminaire, Type "SFP", Submersible Fountain Upright (Flag Pole Lighting)	6 EA. TOTAL UNIT PRICE IN WORDS				\$ -
97	SPL	Luminaire, Type SF, Submersible Fountain Upright Nozzles (Sculpture Wall Nozzle Lighting)	4 EA. TOTAL UNIT PRICE IN WORDS				\$ -
98	SPL	Luminaire, Type "TL" Planting Upright, 240Volts	12 EA. TOTAL UNIT PRICE IN WORDS				\$ -

**APPENDIX A: BID SCHEDULE**  
**PROJECT CIP# LB-17: FIRST RESPONDERS PARK**

Bidder agrees to perform all work described in the Contract Documents for following unit prices or lump sum prices

LINE	ITEM NO.	DESCRIPTION	ESTIMATED QUANTITIES	MATERIAL	LABOR	TOTAL UNIT PRICE OF MATERIAL AND LABOR	TOTAL IN FIGURES
99	SPL	Luminaire, Type "TRU" Trellis Column In Ground Uplight, 120Volts	8 EA.				\$ -
			TOTAL UNIT PRICE IN WORDS				
100	SPL	LED Step Light, Type "ST", Platform Step Lighting, 24Volts	66 EA.				\$ -
			TOTAL UNIT PRICE IN WORDS				
101	SPL	Luminaire, Type "SWL", Tower Steel Piece 0047, 240Volt	8 EA.				\$ -
			TOTAL UNIT PRICE IN WORDS				
102	SPL	Luminaire, Type "SUL", Tower Steel Piece I-0038, 24Volt	8 EA.				\$ -
			TOTAL UNIT PRICE IN WORDS				
103	SPL	LED Light Tube, Type "SW", Planter Wall Lighting, 12Volt	6 EA.				\$ -
			TOTAL UNIT PRICE IN WORDS				
104	SPL	Luminaire, Type "STOR" Storage Area Wall Lighting, 120Volts	4 EA.				\$ -
			TOTAL UNIT PRICE IN WORDS				
105	SPL	Luminaire, Type "SL" (Warm White) Illuminate Sculpture, 24Volts	12 EA.				\$ -
			TOTAL UNIT PRICE IN WORDS				
106	SPL	Luminaire, Type "SL" (Cool White) Illuminate Sculpture, 24Volts	10 EA.				\$ -
			TOTAL UNIT PRICE IN WORDS				
107	SPL	LED Drivers, Q-Set-LED-120-120/12+Dim (2 Required) With Q-Vault Installed in Planting Pit Splice Box, 12Volt	6 LUMP				\$ -
			TOTAL LUMP SUM PRICE IN WORDS				
108	SPL	LED Drivers, Q-Set-LED-200-120/24+Dim (2 Required) With Q-Vault Installed Flush in Pavement, 24Volt	3 EA.				\$ -
			TOTAL UNIT PRICE IN WORDS				
109	625	Light Pole, Decorative, Post For Top Luminaire, 14' height, As Per Plan	8 EA.				\$ -
			TOTAL UNIT PRICE IN WORDS				

**APPENDIX A: BID SCHEDULE**  
**PROJECT CIP# LB-17: FIRST RESPONDERS PARK**

Bidder agrees to perform all work described in the Contract Documents for following unit prices or lump sum prices

LINE	ITEM NO.	DESCRIPTION	ESTIMATED QUANTITIES		MATERIAL	LABOR	TOTAL UNIT PRICE OF MATERIAL AND LABOR	TOTAL IN FIGURES
110	625	Light Pole Foundation, 18"x4', As Per Plan	8	EA.				\$ -
			TOTAL UNIT PRICE IN WORDS					
111	625	Bollard, Decorative, 18 Watt Warm White LED, 120volt	15	EA.				\$ -
			TOTAL UNIT PRICE IN WORDS					
112	625	Bollard Foundation, 18"x3', As Per Plan	15	EA.				\$ -
			TOTAL UNIT PRICE IN WORDS					
113	625	2" Conduit (725.05), Concrete Encased, As Per Plan	150	L.F.				\$ -
			TOTAL UNIT PRICE IN WORDS					
114	625	3" Conduit (725.05), Concrete Encased, As Per Plan	1,600	L.F.				\$ -
			TOTAL UNIT PRICE IN WORDS					
115	625	4" Conduit (725.05), Concrete Encased, As Per Plan	650	L.F.				\$ -
			TOTAL UNIT PRICE IN WORDS					
116	625	Trench, As Per Plan	1,450	L.F.				\$ -
			TOTAL UNIT PRICE IN WORDS					
117	SPL	20 Amp. Recepticle, Flag Base	3	EA.				\$ -
			TOTAL UNIT PRICE IN WORDS					
118	SPL	20 Amp. Dual Recepticles, Planting Pit	6	EA.				\$ -
			TOTAL UNIT PRICE IN WORDS					
119	SPL	Concessionaire 100 Amp. Power Pedestal	1	EA.				\$ -
			TOTAL UNIT PRICE IN WORDS					
120	SPL	Splice Box Type 1, 14" x 23" x 32" Deep, with word "ELECTRIC"	22	EA.				\$ -
			TOTAL UNIT PRICE IN WORDS					
121	SPL	Splice box Type 2, 17" x 30" x 32" Deep, with word "ELECTRIC"	8	EA.				\$ -
			TOTAL UNIT PRICE IN WORDS					

**APPENDIX A: BID SCHEDULE**  
**PROJECT CIP# LB-17: FIRST RESPONDERS PARK**

Bidder agrees to perform all work described in the Contract Documents for following unit prices or lump sum prices

LINE	ITEM NO.	DESCRIPTION	ESTIMATED QUANTITIES	MATERIAL	LABOR	TOTAL UNIT PRICE OF MATERIAL AND LABOR	TOTAL IN FIGURES	
122	SPL	Splice Box Type 3, 24" x 36" x 42" Deep, with word "ELECTRIC"	8 EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS					
123	SPL	Power Service	1 LUMP				\$ -	
			TOTAL LUMP SUM PRICE IN WORDS					
124	625	Material Only (Spare), Luminaire, Decorative Post Top, 150Watt HPS Type III, 240Vatt, As Per Plan	1 EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS					
125	625	Material Only (Spare), Light Pole, Decorative for Post Top Luminaire, 16' height, As Per Plan (Sternberg)	1 EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS					
126	SPL	Material Only (Spare), Bollard, Decorative, 18 Watt Warm White LED, 120volt	1 EA.				\$ -	
			TOTAL UNIT PRICE IN WORDS					
<b>TOTAL</b>								
Total in Words:							10 % Force Account (10% of Total)	

CONTRACTOR \_\_\_\_\_  
 ADDRESS \_\_\_\_\_  
 TELEPHONE \_\_\_\_\_  
 BY \_\_\_\_\_  
 SIGNATURE \_\_\_\_\_

The Bidder's Total Bid on this sheet is for information only at the time of opening bids. The City will make the Total in Figures extensions on the Bid Schedule, and if there is any difference between the Total in Figures, the Total Unit Price in Words shall govern in calculating the Total in Figures.

**NOTE: This proposal shall remain valid, with unit and lump sum prices described herein, for a period of not less than 90 days from the bid opening date. All three (12) pages of this BID SCHEDULE shall become part of the Contract if proposal is accepted by the City of Hilliard. The unit and lump sum prices shall remain valid for the term of the contract.**  
 FED. TAX I.D. # \_\_\_\_\_